



SOUTHERN SANDOVAL COUNTY ARROYO FLOOD CONTROL AUTHORITY

IFB# 2024-03 – Riparia Ponds

ADDENDUM #1

September 9, 2024

This Addendum consists of one (1) page and one (1) attachment. The information contained in this addendum shall be incorporated into the project bid and contract documents the same as if originally contained therein.

Bidders shall acknowledge receipt of this addendum on the Bid Proposal form in the space provided. Failure to acknowledge this addendum by any prospective bidder will render the bid non-responsive.

BID AND CONTRACT DOCUMENTS

- Replace Pages 23-24 of Volume 1 of the Bid and Contract Documents with the attached revised Unit Price Bid Proposal.

All other provisions of the Bid and Contract Documents shall remain unchanged. This Addendum is hereby made a part of the Bid and Contract Documents to the same extent as those provisions contained in the originals.


Andrés Sanchez, PE
SSCAFCA Design Services Director

Attachment:

1. Revised Unit Price Bid Proposal (2 pages)

Unit Price Bid Proposal (Revised with Addendum 1 - 9/9/2024)

Bid Item Number	Item	Estimated Qty	Units	Cost/Unit	Cost	Specification
1	NPDES Compliance	1	LS			SSCAFCA 1511
2	Construction Surveying and Staking	1	LS			SSCAFCA 1514
3	Construction Sign	1	LS			STD DTL
4	Control of Storm Water and Nuisance Flow	1	LS			SSCAFCA 1512
SUBTOTAL GENERAL ITEMS						
5	Clear & Grubbing	15.0	ACRE			APWA 201 STS 201
6	Over-Excavation, Backfill, and Compaction, CIP	7,377	CY			SSCAFCA 1510; STS 204
7	Excavation, Backfill, and Compaction, CIP	39,104	CY			SSCAFCA 1510
8	Excavate and Dispose of Excess Material, CIP	18,000	CY			SSCAFCA 1510
9	Native Grass Seeding, CIP	5.1	AC			APWA 1012; STS 1012
SUBTOTAL EARTHWORK						
10	24" SD Pipe; includes trenching; CIP	261	LF			APWA 123; APWA 910
11	30" SD Pipe; includes trenching; CIP	750	LF			APWA 123; APWA 910
12	42" SD Pipe; includes trenching; CIP	282	LF			APWA 123; APWA 910
13	24" End Section; CIP	1	EA			APWA 123; APWA 910
14	30" End Section; CIP	12	EA			APWA 123; APWA 910
15	42" End Section; CIP	3	EA			APWA 123; APWA 910
16	4' Dia. SD Manhole; CIP	1	EA			APWA 920
17	Flowable Fill; CIP	37	CY			APWA 207
18	Ported Riser #1 (Pond 3 to Channel); CIP	1	LS			APWA 101; STS101
19	Ported Riser #2 (Pond 3 to Pond 2); CIP	1	LS			APWA 101; STS101
20	Class A Riprap (including geotextile); CIP	2,272	CY			NMDOT 602, 604
21	Class A Riprap Subsurface (including geotextile); CIP	1,260	CY			NMDOT 602, 604
22	Class B Riprap (including geotextile); CIP	170	CY			NMDOT 602, 604
23	Class H Riprap (including geotextile); CIP	253	CY			APWA 109
24	Exist. West Rundown and Wall Removal and Disposal; complete	1	LS			SSCAFCA 1515
25	Exist. Unser Channel & Soil Cement Run Down Removal and Disposal; complete	1	LS			SSCAFCA 1515
26	Exist. Soil Cement Berm Removal and Disposal, complete	1	LS			SSCAFCA 1515

27	Temporary Construction Fence; CIP	1,537	LF			SSCAFCA 1501
28	Post and Cable Fence; CIP	191	LF			NMDOT 607; SSCAFCA M104
29	5-strand smooth -wire fence; CIP	2,225	LF			NMDOT 607; SSCAFCA M100
30	Pedestrian Railing; CIP	85	LF			NMDOT 607
31	2" Gravel Mulch, CIP	741	CY			APWA 1012
32	Shotcrete 8" thick (Includes subgrade prep); CIP	3,002	SY			AMAFCA STD DWG C102S APWA 511, APWA 101
33	Structural Concrete (Channel Lining); CIP	527	CY			APWA 101
34	PCC Channel Subgrade prep; CIP	1,359	SY			APWA 301
35	Access Rd 8" Aggregate Base Course , CIP	654	SY			APWA 302
36	Access Rd 12" Subgrade preparation; CIP	1,044	SY			APWA 301
	SUBTOTAL STRUCTURES AND MISCELLANEOUS					
	SUBTOTAL					
37	Mobilization, complete (not to exceed 5% of subtotal)					
	BASE BID SUBTOTAL					
	Testing Allowance				\$ 65,000	
	TOTAL - not including New Mexico Gross Receipts Tax					
	NMGRT 7.4375%					
	TOTAL plus NMGRT					